

NRN Pit

Street Tree
Sewer Manhole

12

14

SCALE @A3 1:200 - LENGTHS ARE IN METRES

10

Water Meter Box (Meter by Owner/Builder)

16

18

20



- 1. This plan has been prepared for information purposes only and does not form part of any contract of sale.
- The lot boundaries & area shown hereon were not marked at the time of publication and have been determined from calculated dimensions only.
- Services shown hereon have been plotted from the latest design information available at the time of publication. The relevant authorities and/or service provider should be contacted for "As Constructed" or DBYD information prior to any design and/or construction of any structure.
- These notes form an integral part of this plan. This plan may not be reproduced unless these notes are included. If others use this information, they should be advised of its purpose and limitations.
- 5. Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company.
- All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.

	Issues	No.	by	Date	Description
		Α	TBG	19/07/18	Original Issue

## saunders havill group

XX.XX

🏿 surveying 🎜 town planning 🗗 urban design 🗗 environmental management 🗗 landscape architecture

Saunders Havill Group Pty Ltd ABN 24 144 972 949

Brisbane Emerald Rockhampton

head office 9 Thompson St Bowen Hills Q 4006

phone 1300 123 SHG web www.saundershavill.com

0

Finished Surface Design Level

## SERVICES AND OTHER FEATURES PLAN

Proposed Lot 1138 on SP300871



Level Datum: AHD der.
Origin of Levels: PM61308
RL of Origin: 54.66
Contour Interval: 0.25m

Scale @A3 1: 200

Dwg No. 7598 S 14 AD A\_1138